SOP – FG Yard Gate System

Oct 23, 2026

Purpose and scope

From Oct 26, 2026 (Monday), control of the Finished Goods (FG) yard moves from Production to the Quality Department, with 100% gate-system implementation.

- **Owner:** Quality Department
- **FG stockyard head:** Mr. Magesh Kumar
- **Applies to:** every machine from Stage 13 completion through FG yard entry, PDI and customer dispatch

Process steps

1. **Stage 13 completion:** After Stage 13 is complete, the machine moves to Testing and Validation.
2. **Return to shop floor:** After Testing and Validation, the machine returns to the shop floor for the UV test and rectification of all quality issues.
3. **Stage 18 clearance:** Quality inspects the machine and clears Stage 18.
4. **Barcode label:** On Stage 18 clearance, the system automatically generates a barcode label from the Quality Department. The label is pasted on the machine.
5. **If any shortage item exists, Quality will NOT clear Stage 18, and the machine CANNOT be moved to the FG yard.**
6. **Move to FG yard gate:** Only an authorised Quality operator (wearing the red or green T-shirt) drives the machine from Stage 18 to the FG yard gate.
7. **Security check at gate:** The security guard at the gate scans the barcode and verifies the operator's T-shirt. If either check fails, the machine is not allowed in.
8. **Location allocation:** When both checks pass, the system allocates an FG yard parking location.
9. **Parking:** The operator parks the machine at the allocated location and returns to the assembly line.
10. **SO-based selection:** Using the FG Yard Stock Status dashboard (developed by IT), the planner selects the part number and quantity against the Sales Order (SO).
11. **FIFO release to PDI:** The system automatically releases machines from the FG yard to PDI on a First-In, First-Out (FIFO) basis.
12. **PDI final check:** The machine undergoes the Pre-Delivery Inspection (PDI) final check.

13. **Dispatch:** After PDI clearance, the machine is dispatched to the customer.

Key control rule

⛔ MANDATORY

If any shortage item exists, Quality will NOT clear Stage 18. The machine CANNOT enter the FG yard.

Roles and responsibilities

Role	Responsibility	Steps
Quality Department	UV test sign-off, Stage 18 clearance, barcode label generation	2–4
Quality operator (red / green T-shirt)	Move machine from Stage 18 to FG yard and park at allocated location	5, 8
Security (FG yard gate)	Scan barcode, verify operator T-shirt, refuse entry if either fails	6
FG stockyard head (Mr. Magesh Kumar)	Overall control of FG yard and gate system	All
Planner	Select part number and quantity against SO in FG Yard Stock Status dashboard	9
IT	Maintain barcode system, location allocation and FG Yard Stock Status dashboard	4, 7, 9–10
PDI team	Final check before dispatch	11
Dispatch	Dispatch PDI-cleared machines to customer	12